

X

4-050325

"CORRECTED"

TO:

API Number: 15-087 00587 00 00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

SW NE SE /4 SEC. 34, 05-S, 27 W
1650 feet from S section line
990 feet from E section line

Operator license# 32334

Lease: N.W. Adell Well # 15

Operator: Chesapeake Operating, Inc.

County: Decatur

Address: 6200 N. Western Avenue
P.O. Box 18496
Oklahoma City, OK 73154
(405) 848-8000

Well total depth 3775 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 236 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Murfin Drilling License# -

Address:

Company to plug at: Hour: A.M. Day: 18 Month: February Year: 1999

Plugging proposal received from: Jeff Wood

Company: Phone:

Were: 10 3/4" surface casing set at 236' with 200 sxs.
7" production casing set at 3762' with 200 sxs.
Perforations at 3793' - 3796'; 3650' - 3724'.

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 2000
8-30-2000
CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 5:00 P.M. Day: 18, Month: February, Year: 1999

Actual plugging report: 01/27/98 - Tied onto 7" casing - pumped 50 sxs 60/40 pozmix - 10% gel 200# hulls, followed with 20 sxs gel and 500# hulls. Perforated at 1450' and 2260'. Pumped 225 sxs cement down casing. Tied onto backside - pumped and squeezed with 100 sxs cement - pressured to 200# - Held. Set 3 hours - tied onto casing. Pumped 150 sxs cement. Well on vaccum. 02-04-99 - Ran wireline top of cement at 1440' - filled casing with fresh water and pressured to 100# - Held. 02-15 to 18-99 - Drilled hole out to 3467' and tied onto 7" casing. Pumped 150 sxs common cement with 2% c.c. Followed with 150 sxs 60/40 pozmix - 10% gel and 1000# hulls. Set CIBP at 3350' - tied onto casing. Pumped and squeezed with 430 sxs cement and 1200# hulls. Max. P.S.I. 500#. S.I.P. 400#.

Remarks:
Condition of casing(in hole): GOOD BAD
Bottom plug(in place): YES, CALC, NO
Plugged through TUBING X, CASING
Any plug: YES X NO
Dakota plug: YES X NO
Elevation: 2858 GL

I did [X] / did not [] observe the plugging.

Mauris Miller
(agent)

Form CP-2/3

CONTINENTAL OIL CO #2 GILLESPIE 'B' 34-5-27W
SW NE SE

Contr. _____ DECATUR County

E. 2662 RB Comm. Comp. 10-24-52 IP 834 B0 & 357 BWPD
PHY POT

Tops	Depth	Datum
HEEB	3612	- 905
LANS	3648	- 986
TD	3775	-1113

Casing
 10" 238
 7" 3762
 DST 3765-75/1 HR, 660'
 SLT WTR, BHP 770#
 PB 3707
 PERF 3678-3700
 PERF 3650-66, 8 BOPH
 3 BWP:
 ACID 500

ADELL NORTHWEST POOL

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS