

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-00210-00-00
Spot: SESESW Sec/Twnshp/Rge: 17-17S-14W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HESTER Well #: 1
County: BARTON Total Vertical Depth: 3408 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 5.5 feet: 3398
SURF Size: 8.625 feet: 881

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2004 12:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: DALE POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 400 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2004 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 325' - 900' - 1600'.
TIH with tubing to 1800' - tied onto and mixed and circulated cement up 5 1/2" with 350 sxs cement and 500# hulls.
POOH. Swaged onto 5 1/2" - pumped 20 sxs cement - circulating cement up 8 5/8".

Perfs:


RECEIVED
DEC 30 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

DEC 27 2004

W C DOENGES, ETAL

#1 HESTER

17-17-14W 52
SE SE SW

Contr. COPPINGER DRILLING, INC BARTON County

E 1898 Comm. 2-18-53 Comp. 5-1-53 IP 40 BOPD

| Tops | Depth | Datum |
|-------|-------|-------|
| HEEB | 3078 | -1180 |
| DOD | 3092 | -1194 |
| BR LM | 3143 | -1245 |
| LANS | 3153 | -1255 |
| | | |
| ARB | 3395 | -1497 |
| | | |
| | | |
| TD | 3408 | -1510 |

Casing

8" 881

DST 3395-3400/1 HR, 8" MUD,
BHP 0#

5" 3398

DST 3399-3404/1 HR, 450" GAS
200' FREE OIL, BHP 245#

GO TD: 750' OIH: AC10 500
SWB 1 BOPH/7 HRS: 2090' FIH/
3 DAYS: SWB 43.12 BO, 10.36
BW/9 HRS: DD 3406: SWB 3 BOPH
NO WTR/19 HRS: DD 3408

CARROLL

| | | |
|---|---|---|
| + | + | + |
| + | + | + |
| + | + | + |

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS