

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-05190-00-00
Spot: SWNW Sec/Twnshp/Rge: 14-15S-14W
3300 feet from S Section Line, 4290 feet from E Section Line
Lease Name: KRAMER C Well #: 3
County: RUSSELL Total Vertical Depth: 3343 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

PROD Size: 5.5 feet: 3338 200 SX CMT
SURF Size: 8.625 feet: 696 300 SX CMT

108⁶⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/28/2004 1:30 PM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, INC.
Proposal Rcvd. from: ALAN CURTIS Company: BEAR PETROLEUM, INC. Phone: (316) 524-1225

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 600# hulls.
Open hole and arbuckle 3338' - 3343'.
Gressel Oilfield Service shot holes at 1550' and 675'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/28/2004 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Dug out backside and rigged a valve and hose to backside.
Tied onto 5 1/2" casing with a swedge and pumped 230 sxs 60/40 pozmix with 250# hulls mixed in to circulate cement out of backside.
Shut in backside and pumped 55 sxs 60/40 pozmix with 50# hulls mixed in.
Max. P.S.I. 250#. S.I.P. 150#.

Perfs:

Top	Bot	Thru	Comments
3338	3343		

RECEIVED
DEC 30 2004
KCC WICHITA

Remarks: COPELAND ACID AND CEMENTING-TICKET #25241.

Plugged through: CSG

District: 04

HO.

Signed *Samuel A. ...*
(TECHNICIAN)

INVOICED
DATE 1-3-05
INV. NO. 2005061025

DEC 29 2004

PHILLIPS PETR CO

#3

C. KRAMER

14-15-14W
CSW NW

Contr.

RUSSELL

County

1895

Comm.

8-21-12

Comp.

9-18-12

IP

2304 BOPD

Tops	Depth	Datum
ANHY	890	
LANS	3093	
ARB	3338	
TD	3342	

Casing

8" 696

5" 3338

A/500

+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

3

11/11/12

5