

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-08663-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 11-9S-17W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: OSWALD Well #: 2
County: ROOKS Total Vertical Depth: 3433 feet

Operator License No.: 4900
Op Name: FINNESY, R. D. DBA FINNESY, R D OIL
Address: 2120 27 ROAD
NATOMA, KS 67651

PROD Size: 5.5 feet: 3424 125 SX CEM
SURF Size: 8.625 feet: 234 175 SX CEM

\$11157

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2004 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: DICK FINNESY Company: FINNESY, R.D. DBA FINNESY RD O Phone: (785) 885-4544

Proposed Plugging Method: Ordered out 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Fluid level 600'.
Squeeze jobs: 01-17-92 w/100 sxs at 2140'; 03-12-81 w/150 sxs at 860'; 12-28-67 w/200 sxs at 820'.
Top of tubing 3063' - unable to fish.
Ran tubing to plug.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2004 11:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1480'.
Allied pumped 120 sxs 60/40 pozmix - 10% gel with 200# hulls.
Circulated cement.
PTOH. Allied squeezed with 155 sxs cement with 200# hulls.
Max. P.S.I. 500#. S.I.P. 300#.
Hooked up to backside. Allied pumped 50 sxs cement with 100# hulls.
Max. P.S.I. 100#. S.I.P. 50#.

Perfs:

RECEIVED
DEC 30 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

101

Signed Richard Williams
(TECHNICIAN)

INVOICED
DATE 1-3-05
INV. NO. 2005061029

DEC 28 2004

OIL PROPERTY MGMT

#2 OSWALD

11-9-17W
SW NW SW

Contr. D & D DRLG

ROOKS County

E. 2009 KB Comm. 4/27/63

Comp. 6/6/63

IP PMP 40 BOPD + 40% WTR
GR 28/ARB 3424-34

LOG Tops	Depth	Datum
* ANHY	1270	+739
TOP	2884	-875
HEEB	3098	-1089
TOR	3123	-1114
LANS	3142	-1133
R/KC	3384	-1375
MARM SD	3393-3404	-1384
ARB	3424	-1415
LTD	3433	-1424

Casing

8" 234/175 sx:
5" 3424/125 sx:


DST 3057-76/1', 15' M, BHP 1026-992#/30", FP 12/26:

DST 3227-50/2', 90' SOCWM, 3' O, BHP 307-240#/30", FP 17-68#:

DST 3417-34/1', 190' O, 60' MCO, BHP 1043-1026#, FP 8/85#:

MINNIE "O"

CQRID 3434: FU 450, O/
12 HRS: A 750 GALS: SWB
3 1/2 BOPH/4 HRS: POP:



* SMP TOP
INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

Vertical text on the left margin, possibly a stamp or reference number, including the word "MINNIE".