

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24576-00-00

Spot: NENESWSW

Sec/Twnshp/Rge: 22-15S-18W

1240 feet from S Section Line,

4195 feet from E Section Line

Lease Name: PIVONKA A

Well #: 7

County: ELLIS

Total Vertical Depth: 3614 feet

Operator License No.: 5127

Op Name: STECKLEIN OIL COMPANY

Address: 579 - 280TH AVENUE
HAYS, KS 67601

PROD Size: 5.5 feet: 3610 110 SX CMT

SURF Size: 8.625 feet: 221 140 SX CMT

#117 46

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/20/2004 1:30 PM

Plug Co. License No.: 99996

Plug Co. Name: ALLIED CEMENT COMPANY

Proposal Rcvd. from: DUANE P STECKLEIN

Company: STECKLEIN OIL COMPANY

Phone: (785) 625-2708

Proposed
Plugging
Method:

Orderd 200 sxs cement - 500# hulls - 20 sxs gel.

Plugging Proposal Received By: HERB DEINES

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/20/2004 3:30 PM

KCC Agent: ROGER MOSES

Actual Plugging Report:

DV tool at 1200' w/210 sxs cement - circulated to surface.
Tied to 5 1/2" casing - pumped 45 sxs cement and 300# hulls.
Pumped 20 sxs gel with 200# hulls.
Squeezed 5 1/2" casing with 130 sxs cement.
Max. P.S.I. 900#. S.I.P. 500#.
Tied to 8 5/8" x 5 1/2" annulus - pressured to 500# - took no cement.
Total of 175 sxs 60/40 pozmix - 10% gel - 20 sxs gel spacer and 500# hulls.
Dakota 232' to 532'. Anhy. 1200' to 1240'.

Perfs:

Top	Bot	Thru	Comments
3358			
3342			
3247			
3229			
0	0		

RECEIVED
DEC 30 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. STECKLEIN OIL-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses
(TECHNICIAN)

INVOICED

DATE 1-3-05

REF. NO. 2005061031

DEC 28 2004

STECKLEIN OIL COMPANY
HAYS, KS 67601

22-15 -18W
1240'FSL & 4195'FEL, SEC

#7 PIVONKA "A"


site: 1 N & 3/4 E OF SCHOENCHEN, KS
contr: RED TIGER DRILLING COMPANY
geol: DUANE STECKLEIN

cty: ELLIS

API 15-051-24576

field: SCHOENCHEN

fr date 01/04/89 spd date 01/04/89 drlg comp 01/11/89 card issued 06/14/89 last revised 06/14/89



ELV: 2037 KB LOG
tops.....depth/datum
HEEB.....3266 -1229
LANS.....3316 -1279
BKC.....3539 -1502
ARB.....3612 -1575
RTD.....3614 -1577

IP status:

OIL, P 10 BO & 10 BWPD, ARB 3610-3614,

CSG: 8-5/8" 221 / 140 SX, 5-1/2" 3610 / 110 SX

NO CORES OR DSTS

MICT - CO, (ARB OH), GSO, T & R, POP, P 10 BO & 10
BWPD (GR 31), 1/28/89

COPYRIGHT 1989
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

WICHITA