

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-20936-00-00
Spot: SESWSE Sec/Twnshp/Rge: 17-9S-18W
330 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HARRISON A Well #: 2
County: ROOKS Total Vertical Depth: 3585 feet

Operator License No.: 32278
Op Name: TENGASCO, INC.
Address: 603 MAIN AVE., STE 500
KNOXVILLE, TN 37902

PROD Size: 4.5 feet: 3583 200 SX CMT
SURF Size: 8.625 feet: 286 175 SX CMT

#11651

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2004 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ED GLASSMAN Company: TENGASCO, INC. Phone: (785) 625-6374

Proposed Plugging Method: Ordered 200 sxs cement and 500# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2004 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

DV tool at 1540' w/550 sxs to surface.
Tied to 4 1/2" casing - squeezed 160 sxs cement with 350# hulls.
Max. P.S.I. 1500#. S.I.P. 1000#.
Tied to 8 5/8" x 4 1/2" annulus - pressured to 750# Max - took no cement.
Total of 160 sxs 60/40 pozmix - 10% gel and 350# hulls.

Perfs:

Top	Bot	Thru	Comments
3583	3585		

RECEIVED
DEC 30 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY. AMERICAN TANK-WATER.

Plugged through: CSG

District: 04

Signed Roger Moses
(TECHNICIAN)

NO.

INVOICED
DATE 1-3-05
INV. NO. 2005041032

DEC 28 2004

17-9-18W
APP SE SW SE

FRONTIER OIL COMPANY #2 HARRISON 'A'
 1720 KANSAS STATE BANK BLDG. WICHITA, KS 67202
 CONTR RED TIGER DRLG. CO. CTY ROOKS
 GEOL JERRY J. KNOBEL FIELD PARADISE CREEK WEST
 E 2164 KB CM 8/8/79 CARD ISSUED 10/13/79 IP P 30 BOPD
 ARB OH 3583 $\frac{1}{2}$ -85

+	+
+	+
+	+
+	+

API 15-163-20,936

SMP	TOPS	DEPTH	DATUM
ANH	1514	+ 650	
BRNVLE	2820	- 656	
TARK	2915	- 751	
HOW	3062	- 898	
TOP	3090	- 926	
HEEB	3300	-1136	
TOR	3320	-1156	
LKC	3340	-1176	
BKC	3546	-1382	
CONG	3559	-1395	
ARB DOL	3582	-1418	
RTD	3585	-1421	

8-5/8" 286/175sx, 4 $\frac{1}{2}$ " 3583 $\frac{1}{2}$ /200sx
 DST (1) 3296-3390/MIS-RUN
 DST (2) 3296-3390/60-60 MIS-RUN
 DST (3) 3293-3390 (TOP)/60-60-60-60,
 240' MSW, SIP 829-779#, FP 81-213/
 203/295#
 DST (4) 3384-3432 (LKC)/60-60-60-60,
 480' MSW, SIP 487-487#, FP 81-233/
 233-264#
 DST (5) 3431-60 (LKC)/60-60-60-60,
 150' MSW, SIP 528-528#, FP 50-71/
 71-91#
 DST (6) 3457-3504 (LKC)/60-60-60-60,
 240' MSW, SIP 708-748#, FP 40-162/
 NO FFP

(OVER)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

FRONTIER OIL COMPANY #2 HARRISON 'A' 17-9-18W APPX SE SW SE
 DST (7) 3502-57 (BKC)/60-60-30-60, 25' SWM W/FEW SPKS O, SIP
 799-608#, FP 40-60/60-60#
 DST (8) 3555-85 (CONG-ARB)/60-60-60-60, 482' CL GSY O, 126' HO
 & GCM, SIP 1030-989#, FP 50-142/203-264#
 MICT - CO, (ARB OH), SWB 2 $\frac{1}{2}$ BOPH, NAT, POP