

4-041540

11-9

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-039-20,890 -00-00

NE SE NW /4 SEC. 01, 05 S, 27 W
1650 feet from S section line
2310 feet from E section line

Operator license# 30912

Lease Noone well # 1

Operator: Alfred Ward & Son Operating

County Decatur

Address: P.O. Box V
Akron, CO 80720

Well total depth 3790 feet ^{123.17}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 300 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Emphasis Oil Operations License# 8241

Address: _____

Company to plug at: Hour: A.M. Day: 5 Month: November Year: 93

Plugging proposal received from: Larry Langhoffer

Company: Emphasis Oil Operations Phone: _____

Were: Order 200 sxs. 60/40 pozmix with 6% gel and 1/4# F.C.
Spot plugs through drill pipe with heavy mud between all plugs.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00A.M., Day: 9, Month: November, Year: 93

Actual plugging report:
1st. plug @ 2650' w/25 sxs.
2nd. plug @ 1400' w/100 sxs.
3rd. plug @ 300' w/40 sxs.
4th. plug @ 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

RECEIVED
STATE CORPORATION COMMISSION

NOV 19 1993

11-19-93
CONSERVATION DIVISION
Wichita, Kansas

Remarks: _____
Condition of casing(in hole): GOOD BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING . Elevation: GL

I did [X] observe the plugging.

Dennis L. Hamel

100

(agent)

Form CP-2/3

INVOICED
DATE NOV 23 1993
INV. NO. 39310