

6010168

API NUMBER 15-137-20339-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE NW^W, SEC. 11, T 5 S, R 25 W

990 feet from NS section line

660 feet from WE section line

Lease Name Marion Goldsby Well # 2-11

County Norton

Well Total Depth 4020 130.65 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 7/8 feet 320

TECHNICIAN'S PLUGGING REPORT

Operator License # 9123

Operator: Diamond Shamrock

Name & Address Box 631

Amarillo Texas

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well (D&A)

Other well as hereinafter indicated _____

Plugging Contractor Diamond Shamrock License Number 9123

Address Same

Company to plug at: Hour: 3 AM Day: 8 Month: 7 Year: 19 84

Plugging proposal received from Pete Coates

(company name) Diamond Shamrock 913 (phone) 674-2141

were: order 210 sx cement 50/50 permix 6% Gel. 3% c.c.
1 sx hulls 1.8 5/8 plug 1.5x Flow Seal

Heavy mud between all plugs.

Pump cement down drill pipe

Elev. 2509 Anhydrite 2109- Arbuckle 3974

Dakota 1450 Plugging Proposal Received by Dale F. Balthazor
(TECHNICIAN)

1059 = 1360

Plugging Operations attended by Agent?: All _____ (Part) _____ None _____

Operations Completed: Hour: 11:45 AM Day: 8 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 3980 for 30 mi

25 sx @ 3980

25 sx @ 2120

100 sx @ 1360 mixed with 7sx Flow seal

40 sx @ 350 Dumped 7sx hulls, pushed plug to 40'

10 sx @ 40

Remarks: 10sx in Rat Hole. Cementing w. Halliburton
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-25-84

INV. NO. 2635

RECEIVED
JUL 16 1984
07-16-1984
CONSERVATION DIVISION
Wichita, Kansas

Dale F. Balthazor
(TECHNICIAN)

July 13 84
9