

4-071005

9-20

179  
R

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-039-20,884 -00-00  
SW SE NE /4 SEC. 11, 05 S, 27 W  
2290 feet from S section line  
980 feet from E section line

Operator license# 30912 Lease McKenna well #1-11

Operator: Alfred Ward & Son Operating County Decatur

Address: P.O. Box V Well total depth 3850 feet 125.12  
Akron, Colorado 80720 Conductor Pipe: 0 inch @ 0 feet  
Randy Ward Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well     , Gas well     , Input well     , SWD     , D & A X

Plugging contractor: Emphasis Drilling License# 8241

Address: Russell, Kansas 67665

Company to plug at: Hour: P.M. Day: 20 Month: September Year: 92

Plugging proposal received from: Jack Fox

Company: Emphasis Drilling Phone:                     

Were: 8 5/8" - 266' S.P. cwc. w/160 sx. 60/40 pozmix - 2% gel. -  
3% c.c. By Allied Cement. No ar buckle. Elv. 2671'. Anhy. 2243'.  
No circulate problems. Mud condition - 50 vis. - 9.2 weight - 10.1 water  
loss. Proposal 25 sx. @ 2250' - 100 sx. w/1 sx. F.C. @ 1470' -  
40 sx. @ 315' - 10 sx. @ 40' - 15 sx. in rathole (circulate).  
Spot with drill stem - circulate hole - heavy mud between all plugs.

Plugging Proposal Received by: Marion J. Schmidt

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 3:00P.M., Day: 20, Month: September, Year: 92

Actual plugging report: Ordered 190 sx. 60/40 pozmix - 6% gel. - 1 sx.  
flocele. Spotted with drill stem, circulated hole, heavy mud between  
all plugs.

1st. plug @ 2250' w/25 sx. cement.  
2nd. plug @ 1470' w/100 sx. cement w/1 sx. F.C.  
3rd. plug @ 315' w/40 sx. cement.  
4th. plug @ 40' w/10 sx. cement.  
15 sx. in rathole (circulate hole).

Remarks: Cemented by: Allied Cement.

Condition of casing(in hole): GOOD X BAD      Anhy. plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING X, CASING     . Elevation: 2671 GL

I did[      ] / did not[ X ] observe the plugging.

DATE 10-12-92

INV. NO. 36415

102-92  
RECEIVED  
STATE CORPORATION COMMISSION  
2 1992  
CONSERVATION DIVISION  
Wichita, Kansas  
*Marion J. Schmidt*  
(agent)