

4-032322

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

10-22

API Number: 15-039-00,577-00-00

NW NW NW /4 SEC. 23, 05, 27 W  
4950 feet from S section line  
4950 feet from E section line

Operator license# 5058

Lease: Danley Well # 1

Operator: Griggs Oil, Inc.

County: Decatur 127-08

Address: 209 E. Williams - Suite #220  
Wichita, Kansas 67202

Well total depth 3910 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 225 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling Company License# 30606

Address: Hill City, Kansas 67642

Company to plug at: Hour: A.M. Day: 22 Month: October Year: 1998

Plugging proposal received from: Wilbur Berg

Company: Griggs Oil, Inc. Phone: -

Were: Order 240 sxs 60/40 pozmix - 10% gel - 700# hulls - 11 sxs gel.  
Allied Cement Company.  
Order work string.

RECEIVED  
OCT 22 1998  
PLUGGING DIVISION  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All , Part , None

11-9-98

Completed: Hour: 11:15 A.M., Day: 22 Month: October Year: 1998

Actual plugging report: 8 5/8" set at 225' w/ 75 sxs cwc. 5 1/2" set at 3910' w/125 sxs. PBTD 3851'. Numerous squeezes behind 5 1/2" before and 4 1/2" liner was run to 3625' with 20 sxs. Prod.perfs 3661'- 3749' (7 sets). Critical area control shots at 2300' and 1460'. Ran tubing to 3300' - spotted 40 sxs cement blend with 250# hulls. Pulled to 1400' - displaced 11 sxs gel. Pulled to 1200' and circulated with 60 sxs cement blend with 250# hulls mixed in. Lay down tubing - topped off 4 1/2" with 15 sxs cement blend. Cut off 8 5/8"- 5 1/2"- 4 1/2". Topped off with 45 sxs cement blend. All strings of casing. Full. Plug complete.

Remarks:  
Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did  / did not  observe the plugging.

Carl Goodrow  
(agent)

D.

11-13-98  
60342