

12-6 15-039-00047-00-00

R

To: **6 041262**  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA

E/2 NE NE, SEC. 22, T 5 S, R 27 W/EX  
4620 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6622

Lease Name Hardesty Well # 1

Operator: Jason Oil Inc.  
Name & Address: Box 701  
Russell, Ks. 67665

County Decatur 125.45  
Well Total Depth 3860 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 269 w/200 sks

Abandoned Oil Well xx Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Ct. License Number \_\_\_\_\_  
Address Oberlin, Ks.

Company to plug at: Hour: 10:30 AM Day: 6 Month: Dec Year: 19 90

Plugging proposal received from Jim Schoenberger

(company name) Jason Oil (phone) \_\_\_\_\_

were: 5 1/2 casing set at 3860 w/250 sks cement: perfs at 3642  
O.H. to 3814; <sup>Perf</sup>Anhy at 2028; Sq from 1455 - 2950; w/1200 sks cement. Ordered  
300 sks 65/35 poz 10% gel plus 6 sks hulls plus 25 gel.

Plugging Proposal Received by Dennis L. Hamel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:45PM Day: 6 Month: Dec. Year: 19 90

ACTUAL PLUGGING REPORT Pumped in 5 1/2 casing w/25 sks cement  
plus pumped in add 225 sks cement w/1/2 lbs f.c. and 400 lbs hulls mixed in cement.  
Max 700 lbs. S.I. 300 lbs. Pumped in 8 5/8 casing w/50 sks cement w/1/2 lb f.c. and  
200 lbs. hulls mixed in cement. Max 200 lbs. S.I. 75 lbs.

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

I (did / did not) observe this plugging.

DATE JAN 17 1991

INV. NO. 30512

12-6

MAR 07 1991

Signed Dennis L. Hamel  
(TECHNICIAN)

Dennis L. Hamel