

4-032052

15-039-00401-00-00

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- -

S2 SW SW /4 SEC. 14 , 05 S, 27 W
330 feet from S section line
4620 feet from E section line

Operator license# 5058

Lease Maher-Feeley well # 2

Operator: Griggs Oil, Inc.

County Decatur

Address: 100 N. Main - #1010
One Main Place
Wichita, Kansas 67202

Well total depth 3770 feet ^{122.53}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet
w/150 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton License#

Address: Hays, Kansas 67601

Company to plug at: Hour: A.M. Day: 6 Month: April Year: 95

Plugging proposal received from: Wilbur Burk

Company: Griggs Oil, Inc. Phone:

Were: Order 350 sxs. 60/40 pozmix - 10% gel - 500# hulls.

STATE CORPORATION COMMISSION
RECEIVED
APR 14 1995
CONSERVATION DIVISION
WICHITA, KANSAS

4-14-95

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 11:00A.M., Day: 6, Month: April, Year: 95

Actual plugging report: 8 5/8" set @ 212' w/150 sxs. cwc. 5 1/2" at
3770' w/125 sxs. Perfs. 3694' - 3711'. PBSD at 3700'. Shot critical
area control shots at 2250' - 1500'. Squeezed 5 1/2" with 270 sxs.
cement blend with 500# hulls mixed into Max. P.S.I. 750#. Close in
P.S.I. 250#. Squeezed 8 5/8" w/80 sxs. to Max. P.S.I. 400#.
Close in P.S.I. 200#. Plug complete.

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] / did not [] observe the plugging. Carl Goodrow

INVOICED

DATE 4-25-95
INV. NO. 42688

HO

(agent)
Form CP-2/3