

10-9

299  
R

4- 031593

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-039-20,311-00-01

N2 SE SE 1/4 SEC. 15, 05 S, 28 W  
990 feet from S section line  
660 feet from E section line

Operator license# -

Lease Ben Ritter Project well # 1

Operator: Kansas Corp. Commission  
Fee Fund

County Decatur

Address: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

Well total depth 1930 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 275 feet

Aband. oil well    , Gas well ?, Input well    , SWD    , D & A    

Plugging contractor: State Corporation Commission License# -

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 9 Month: October Year: 91

Plugging proposal received from: Carl Goodrow

Company: K.C.C. Conservation District Phone: \_\_\_\_\_

Were: 8 5/8" set @ 275 w/175 sx. cwc. 4 1/2" set @ NA recovered rods  
and tubing from 1960'. Tag T.D. @ 1960'. Perfs. in Cheyenne sand.  
Ordered 250 sxs. 65/35 posmix - 10% gel. - 500# hulls. Allied Cement  
Company. LaRue Water Trucks. This was a Cheyenne Sand Gas Test Well.  
This was D & A. Bottom collapsed and was cemented to K.C. for Dst, then  
well was plugged. The pipe set without records of re-entry.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All  ], Part  ], None  ]

Completed: Hour: 3:00P.M., Day: 9, Month: October, Year: 91

Actual plugging report: Pumped down tubing from 1960' to surface with  
cement blend. Laid down tubing. Squeezed 4 1/2" casing with total 200  
sxs. cement blend w/200# hulls mixed in to max. P.S.I. 1500#.  
Close in P.S.I. 1500#. 8 5/8 annulus was full of cement.  
Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

11-4-1991  
NOV 4 1991

Remarks: Cheyenne Sand Test For Gas.

I did  / did not  observe the plugging. Carl Goodrow

*Phil S.*

(agent)