

3-3-88 15-039-19055-00-00
121

6 031045

API NUMBER 15- 1952

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE NE SE SEC. 34, T 5 S, R 27 (W/E)

2310 feet from S section line

320 feet from E section line

Lease Name NW Adell Unit Well # 13

County Decatur 125.98

Well Total Depth 3870 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 247

TECHNICIAN'S PLUGGING REPORT

Operator License # 5916

Operator: Conoco Inc.

Name & Address 3817 N.W. Expressway

Oklahoma City, Ok. 73112

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address Oberlin, Kansas

Company to plug at: Hour: AM Day: 3 Month: Mar Year: 19 88

Plugging proposal received from David Lorenzo

(company name) Conoco (phone) _____

were: 10 3/4" casing set at 247' cwc 200 sks. 5 1/2" csg set at 3869' w/200 sks.

PBTD 3837'. Perf at 1400' for Dakota protection. Order 250 sks

Econolite Cement Blend 65/35 Poz 10% Gel 2% Dicel 5 sks Hulls. Halliburton Cement

Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:00AM Day: 3 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" csg w/200 sks Cement Blend

w/5 sks Hulls mixed into Max Psi 150%. Close in Psi 150%. Squeeze annulus

10 3/4" - 5 1/2" w/50 sks Cement Blend to Max Psi 150%. Close in Psi 150%. Plug

complete.

RECEIVED
STATE CORPORATION COMMISSION
4-22-88

APR 22 1988

Remarks: _____

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-26-88

INV. NO. 20638

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

D