

3-3-88 15-039-19034-00-00  
1300 R

6 031044

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 1952  
NE NE NE, SEC. 34, T 5 S, R 27 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5916  
Operator: Conoco Inc.  
Name & Address: 3817 NW Expressway  
Oklahoma City, Oklahoma  
73112

4950 feet from S section line  
330 feet from E section line  
Lease Name NW Adell Unit Well # 5  
County Decatur 125.81  
Well Total Depth 3871 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 10 3/4 feet 245

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number  
Address Oberlin, Kansas

Company to plug at: Hour: PM Day: 3 Month: Mar Year: 19 88

Plugging proposal received from David Lorenzo

(company name) Conoco (phone)

were: 10 3/4" set at 245' cwc 200 sks. 7" csg set at 3869' w/200 sks. PBTD  
3608'. Perf at 1390' for Dakota protection. Order 300 sks Econolite Cement Blend 65/35  
Poz 10% Gel 2% Dixel 5 sks Hulls. Halliburton Cement Co. LaRue Water Truck.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:15PM Day: 3 Month: Mar Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 7" csg w/250 sks Cement Blend w/5 sks  
Hulls mixed into Max Psi 500#. Close in Psi 300#. Squeeze annulus 10 3/4" - 7" w/50 sks Cement  
Blend to 300#. Close in Psi 150 #. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
4-22-88  
APR 22 1988

Remarks: (If additional description is necessary, use BACK of this form.)

did not observe this plugging.

DATE 4-26-88  
INV. NO. 20437

Signed Carl Goodrow  
(TECHNICIAN)