

4-13 15-039-30099-00-00

6 031239

API NUMBER 15- 1959

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SE NE, SEC. 27, T. 5 S, R 27 W/E
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7448

Lease Name Feeley Well # 1

Operator: Burch Exp Inc.
Name & Address: 11225 Edinborough Way
Parker, Colorado 80134

County Decatur 124.96
Well Total Depth 3845 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 215

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Poe's Servicing, Inc. License Number 6779 3152
Poe Well Service

Address Oberlin, Ks. P.O. Box 218 - Oakley, KS 67748

Company to plug at: Hour: AM Day: 13 Month: April Year: 19 89

Plugging proposal received from Mel Taylor

(company name) Burch (phone)

were: 8 5/8" set at 215' w/150 sks. 4 1/2" set at 3844' w/150 sks. PBTD 3834'.
Perf 3634' - 36'. Order 50 sks common cement 175 sks 65/35 Poz 10% Gel 2% Dixel
500# Hulls. Halliburton Cement Company. LaRue Water Truck.

MAY 10 1989 S-10-89

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)
Wichita, Kansas

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00AM Day: 13 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Squeeze 4 1/2" w/50 sks common cement w/500# Hulls
mixed in followed by 120 sks cement blend. To max psi 400#. Close in psi 200#. Squeeze
8 5/8" annulus w/80 sks cement blend to max psi 300#. Close in psi 300#. Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 5-11-89

INV. NO. 24757

Jeb.S

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

JUN 12 1989