

To: 6 031238
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-12 15-039-20036-00-00
API NUMBER 15- 1968

C N/2 NW NE, SEC. 27, T. 5 S, R. 27 W/E
4950 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7448

Lease Name Feeley Well # 4
County Decatur 127.56
Well Total Depth 3925 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 7 feet 212

Operator: Burch Exp Inc.
Name & Address 11225 Edinborough Way
Parker, Colorado 80134

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor ~~Poe Well Service~~ Poe's Servicing, INC. License Number 6779-3152 *KEC 1/2*

Address Oberlin, Ks. Box 218, OAKLEY 67748

Company to plug at: Hour: 4:00 PM Day: 12 Month: April Year: 19 89

Plugging proposal received from Mel Taylor

(company name) Burch (phone) _____

were: 7" set at 212' w/150 sks. 4 1/2" set at 3924' w/150 sks. PBDT 3879'.

Perf 3688' - 3808'. Order 50 sks common cement 175 sks 65/35 Poz 10% Gel 2% Dical 500# Hulls. Halliburton Cement Co. LaRue Water Trucks.

5-10-89
MAY 10 1989

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:00PM Day: 12 Month: April Year: 19 89

ACTUAL PLUGGING REPORT Squeeze 4 1/2" w/50 sks common cement w/500# Hulls mixed in followed w/95 sks cement blend to max psi 300#. Close in psi 150#. Squeeze 7" annulus w/80 sks cement blend to max psi 300#. Close in psi 100#. Plug complete.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-11-89
INV. NO. 24756
4-12

Jim S

Signed Carl Goodrow
(TECHNICIAN)
Carl Goodrow

JUN 12 1989