

4-14
4-050306

15-039-00579-00-01

E-15,099-0001

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

RECEIVED
KANSAS CORP COM
SW SE SE /4 SEC 27 005 S, 27 W
330 feet from S section line
990 feet from E section line

04-17-98

Operator license# ~~3871~~ 3871
Operator: Chesapeake Operations, Inc.
Address: 1036 E. Highway 40
Hays, Kansas 67601
785-625-1798

Lease: NW Adell Well # 3
County: Decatur 126.10

Well total depth 3880 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 10 3/4 Inch @ 247 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: _____

Company to plug at: Hour: A.M. Day: 14 Month: April Year: 1998

Plugging proposal received from: Chris Gottschalk

Company: Chesapeake Operations, Inc. Phone: 785-625-1798

Were: Order 300 sxs 60/40 pozmix - 10% gel and 500# hulls.
10 3/4" set at 247' w/200 sxs. 5 1/2" set at 3879' w/150 sxs.
Perfs 3648' - 3841'. PBSD 3788'.
Squeezed at 320' w/150 sxs - 2575' w/250 sxs - 2445' w/350 sxs.
Packers in hole at 3637' and 3710'. Bridge plug at 3620'.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All , Part , None

Completed: Hour 12:15 P.M. Day: 14, Month: April, Year: 1998

Actual plugging report: Tied onto 5 1/2" casing - pumped and squeezed 300 sxs cement and 500# hulls. Max. P.S.I. 800#. S.I.P. 100#.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES , CALC _____, NO _____ Dakota plug: YES , NO _____
Plugged through TUBING _____, CASING . Elevation: 2660 GL

I did / did not observe the plugging.

Maurice Miller
(agent)

OK

Form CP-2/3

INVOICED

DATE 4-21-98

INV. NO. 50368

4-14