

State of Kansas



15-137-00278-00-00 FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 10 1962

12-10-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Buck Wenrich of D & D Drg Co has this

date requested permission to plug the following described well:

Mr. Wenrich guarantees payment of the plugging fee.

Operator's full Name: D & D Drg Co

Complete Address: 308 Schweiter Bldg Wichita, Kans

Lease Name: Archer Well No. 1

Location: NE NE SW Sec. 1 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 3555 Oil Well

Gas Well Input Well SWD Well D & A x Lost Hole

Mr. Wenrich was instructed to plug the well as follows:

8 5/8" 215' circulated with cement.

Circulate hole with heavy mud, set plug at 550' with 20 sac cement

"	"	200'	20	"
"	"	40'	10	"

Very truly yours,

Eldon Petty
Conservation Division Agent