



15-137-20052-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1970  
CONSERVATION DIVISION  
Wichita, Kansas

12-10-70

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Csg. Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Leben Drilling, Incorporated,

Complete Address: Box #486, Great Bend, Kansas.

Lease Name: Allen Well No. A-1

Location: CNW-NE Sec. 2 Twp. 5 Rge. (E)(W) 22

County: Norton Total Depth 3508' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3505'--5 1/2" Production casing cemented on bottom with 100 Sx. No plug back indicated nor perforations.

Push plug to 3200' sand back to 3175' and set 5 Sx. cement with dump trailer.  
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

  
Conservation Division Agent