



15-137-20263-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

STATE RECEIVED
OCT 07 1982
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Jerry Helberg of Helberg Oil Co. #269 has this

date requested permission to plug the following described well:

Operator's Full Name: Ozark Enterprises

Complete Address: Box 427, Logan, Mo. 67646

Lease Name: Noone Well No. A #1

Location: C of NW-NE Sec. 14 Twp. 5 Rge. 22 (E) (W)

County: Morton Total Depth: 3613'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Helberg was instructed to plug the well as follows:

8 5/8" - 202' S.P. core w/ 125 sacks common - 2% Gel - 3% Cal. Cl.
Ordered 170 sacks 50% posmix - 6% Gel - 3% Cal. Cl. + 8 5/8" plug. Spot w/ drill
stem w/ heavy mud between all plugs. 1st plug C 1050' w/ 100 sacks:
2nd plug C 250' w/ 40 sacks
3rd plug - solid bridge of balls + plug C 40' w/ 10 sacks
Circulate 10 sacks in rat hole

Very truly yours,

[Signature]
Conservation Division Agent