

State of Kansas



15-137-20011-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION DIVISION

NOV 29 1961

11-29-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management, Incorporated,

Complete Address: 1515 Wichita Plaza, Wichita, Kansas.

Lease Name: Robinson Well No. 1

Location: NE-NE-SW Sec. 20 Twp. 5 Rge. (E)(W) 22

County Norton Total Depth 3845' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

210'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Dakota section from 1275' to 1475'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.
cement thru DP. Pull DP to 220' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent