



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-127-00315-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name: Veeh Well No. A-10

Location: SW-NE-NE Sec. 36 Twp. 5 Rge. (E)(W) 21

County: Horton Total Depth 3659 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

205'--8 5/8" Surface casing, cement circulated with 250 Sx.
3655'--5 1/2" Production casing cemented on bottom with 150 Sx. No plug back nor perforations indicated.

Sand back to 3615' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze hole with 5 sacks hulls, 25 sacks gel and 180 Sx. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent