



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 30 1972  
05-31-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-20081-00-00

Dear Sir:

Mr. Wilmer Dreiling of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Dreiling guarantees payment of the plugging fee.

Operator's full Name: Lee Phillips Oil Company,

Complete Address: 125 North Market, Suite 1532, Wichita, Kansas.

Lease Name: Jacobson Well No. 1

Location: NE-SW-NE Sec. 34 Twp. 5 Rge. (E)(W) 21

County: Norton Total Depth 3728' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Dreiling was instructed to plug the well as follows:

251'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols  
Conservation Division Agent