

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-137-20058-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUL 7 1970
CONSERVATION DIVISION
Wichita, Kansas
7-7-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Co.

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas

Lease Name Ryan Well No. 1

Location SW NE NE Sec. 16 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 1707

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Dreiling Oil Co.

Address Victoria, Kansas License No.

Operation Completed: Hour 2:45P Day 5 Month 7 Year 1970

The above well was plugged as follows:

RTD 1707' 8 5/8 csg set at 288' cwc Cmt. Mat. 100 sk reg poz 6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 270' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 7/7/70
INV. NO. 2182-W