

STATE CORP. COMMISSION
RECEIVED
OCT 09 1982
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

KANSAS

FORM CP-3
Rev. 1-8-82

CONSERVATION DIVISION AGENT REPORT

10-7-82

API Number 15-

No Drilling Intent
15-137-20263-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Ogark Enterprises

Complete Address P.O. Box 427, Logan, Ks. 67646

Lease Name Noone Well No. A #1

Location C of NW NE Sec. 14 Twp. 5 Rge. 22 (East (West))

County Norton Total Depth 3613'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Helberg Oil Co.

Address Box 32, Morland, Ks. 67650 License No. 269

Operation Completed: Hour: 1:45 AM Day: 25 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

by Carl Goodrow

The above well was plugged as follows:

8 5/8" 202' SP. case w/125 sacks common - 2% Jel. - 3% Cal. U.

Ordered 170 sacks 50 posmix - 6% Jel. - 3% Cal. U. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug C 1050' w/100 sacks

2nd plug C 250' w/40 sacks

3rd plug - solid bridge of hulls & plug C 40' w/10 sacks.

Circulate 10 sacks in rat hole & 10 sacks in mouse hole.

Amount of Surface Casing: 202' of 8 5/8"

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-20-82

INV. NO. 1430-w