

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-137-20092-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUN 20 1974
6020-74
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name R. P. Nixon

Complete Address Box 589, Russell, Kansas

Lease Name McKinley Well No. 1

Location NE NW SE Sec. 24 Twp. 5 Rge. (E) (W) 22

County Norton Total Depth 3715'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Shields Drdg.

Address Russell, Kansas License No.

Operation Completed: Hour 8 A Day 18 Month 6 Year 1974

The above well was plugged as follows:

RTD 3715' 8 5/8 csg set at 200' cwc 150 sk.

Gunned pits, circulated heavy mud, set cementing plug at 1075' and displaced 70 sk cmt thru drill pipe. Heavy mud to 185' set cementing plug and displaced 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: L. J. Moseley
Well Plugging Supervisor

RECORDED

DATE 6/24/74

INV. NO. 9365-W