

KANSAS

*J*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 30 1972  
05-30-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-137-20081-00-00

Operator's Full Name Lee Phillips Oil Company,

Complete Address 125 North Market, Suite 1532, Wichita, Kansas.

Lease Name Jacobson Well No. 1

Location NE-SW-NE Sec. 34 Twp. 5 Rge. (E) (W) 21

County Norton Total Depth 3728'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Gabbert-Jones, Incorporated,

Address 830 Sutton Place, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 2:00 PM Day 27 Month 5 Year 1972

The above well was plugged as follows:

251'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1000'.

Circulated hole with heavy mud. Pulled DP to 1225' and displaced 110 Cu. Ft. cement  
thru DP from 1225' to 900'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 5/31/72  
INV. NO. 5765-41