

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
CORPORATION COMMISSION  
SEP 22 1971  
09-22-1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-137-00315-00-00

Operator's Full Name Cities Service Oil Company,

Complete Address Box #553, Russell, Kansas.

Lease Name Veeh Well No. A-10

Location SW-NE-NE Sec. 36 Twp. 5 Rge. (E) (W) 21

County Morton Total Depth 3659'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling, Incorporated,

Address Box #405, Chase, Kansas License No. 624

Operation Completed: Hour 5:00 PM Day 20 Month 9 Year 1971

The above well was plugged as follows:

205'--8 5/8" Surface casing, cement circulated with 250 Sx.

3655'--5 1/2" Production casing cemented on bottom with 150 Sx. No plug back nor perforations indicated.

Sanded well back to 3615 and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (596') and squeezed well initially with 5 sacks hulls and 13 sacks gel then 105 Sx. cement from 1060' to 725', followed with 12 sacks gel from 725' to 245' and finally 75 Sx. cement from 245' to bottom of cellar. Maximum pump-in pressure--200#. Final shut-in pressure--100#. (Mudding and cementing by Allied Cementing, Inc.,).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols  
Well Plugging Supervisor

DATE 9-22-71

INV. NO. 4355-W