

15-039-00010-06-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas


OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plugging  
off formations.

Decatur County, Sec. 11 Twp. 5S Rge. 27W(E) (W)

NORTH



Locate well correctly on above  
Section Plat

Location as "NE1/4NW1/4SW1/4" or footage from lines  
Lease Owner: Sterling Drilling Co.  
Lease Name: Randall Well No. 1  
Office Address: Sterling, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole): Dry hole  
Date well completed: October 1, 1944  
Application for plugging filed: October 2, 1944  
Application for plugging approved: October 2, 1944  
Plugging commenced: October 3, 1944  
Plugging completed: October 3, 1944  
Reason for abandonment of well or producing formation: Dry

If a producing well is abandoned, date of last production: \_\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes (Telephone)

Name of Conservation Agent who supervised plugging of this well: \_\_\_\_\_  
Producing formation: \_\_\_\_\_ Depth to top: \_\_\_\_\_ Bottom: \_\_\_\_\_ Total Depth of Well: 4144 Feet  
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
	Surface pipe			10 3/4	265	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged with 250 sacks cement



10-19-1944

(If additional description is necessary, use BACK of this sheet)  
Correspondence regarding this well should be addressed to: Sterling Drilling Company  
Address: Sterling, Kansas

STATE OF Kansas, COUNTY OF Rice, ss.  
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) F. A. Wuellner  
Sterling, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 18th day of October, 1944

My commission expires Feb. 23, 1948  
Josephine Stevenson Notary Public

15-039-00010-00-00

Total Depth 4144  
Commenced Sept. 5, 1944  
Completed October 1, 1944  
Contractor, Sterling Drilling Company  
Casing 265 ft, Surface pipe 10 3/4"

Sec. 11-5S-27W  
CW/2 NE/4 SW/4  
Decatur County, Kan.  
Elevation 2636 Rig floor

0-280	Clay & Shale
180-965	Shale
965-1165	Shale & Shells
1165-1450	Sandy Lime & Shale
1450	Lost circulation
1450-1590	Shale
1590-1710	Shale & Lime
1710-1800	Lime
1800-2050	Red Rock & Shale
2050-2205	Shale & Red Rock
2205-2290	Lime (Hard)
2290-2690	Shale
2690-2815	Lime & Shale
2815-2935	Shale
2935-3011	Lime & Shale
3011-3040	Lime
3040-3061	Shale
3062-3129	Lime
3129-3190	Lime & Shale
3190-3340	Shale
3340-3455	Lime
3455-3470	Red Shale
3470-3628	Lime
3628-3683	Lime
3683-3851	Lime & Shale
3851-3922	Red Shale & Lime
3922-4052	Red Shale
4052-4118	Lime
4118-4125	Dark Red Shale
4125-4130	Very sandy Shale
4130 4132	Coarse Sand
4132 4144	Pink Granite

Production. dry hole

Sample tops corrected  
to derrick floor

2210	Top Anhydrite
3360	Top Topeka
3586	Heebner Shale
3612	Lansing-KU
3825	Base KC
4044	Arbuckle
4110	Base Arbuckle
4129	Basal Sand
4131	Pre Cambrian Granit
4144	TD

T D

10-19-44

**PLUGGING**  
 FILE 11-5-27W  
 BOOK PAGE 134 LINE 21