

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market - Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-187-10014-0000

LEASE NAME MASON

WELL NUMBER 2-1

1260' FSL Ft. from S Section Line

1260' FEL Ft. from E Section Line

SEC. 1 TWP. 31S RGE. 38W (E) or (W)

COUNTY STEVENS

Date Well Completed 6/18/59

Plugging Commenced 11/15/04

Plugging Completed 11/19/04

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # 972) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9/07/04 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation COUNCIL GROVE Depth to Top 3113' KB Bottom 2880' T.D. 5803'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

*KCC
SEM
12/10/04
RDMO
RUC 4/3*

Formation	Content	From	To	Size	Put in	Pulled out
COUNCIL GROVE	GAS	2773'	2863'	13 3/8"	576'	0
				8 5/8"	2990'	918'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set

11/17-19/04 P&A Op - KCC notified. POOH tbq. rods. subs. Cmtr to 8 5/8" csg. Load hole w/160 bbl 9 ppg 36cp mud, cut csg 918'. Circ w/90 bbl mud + 50 sx cmt plug 945'-875'. Disp w/4 bbl mud. Pmp 75 sx cmt 600'-500'. Disp w/2 bbl mud. Pmp 25 sx cmt 40' to 0'. Cut 13 3/8" csg 3' bgl, weld trash cover ID plate. RDMO.

Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.


LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Linda Kelly

(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 20 04

My Commission Expires: 3/23/06 F. Jean Kelly Notary Public



Form CP-4
Revised 05-88