

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-039-19034-00-00
 API NUMBER _____

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME N.W. Adell Unit

WELL NUMBER 5

330 Ft. from ^N Section Line

330 Ft. from E Section Line

SEC. 34 TWP. 53 RGE. 27 or (W)

COUNTY Decatur

Date Well Completed 6-24-52

Plugging Commenced 3-3-88

Plugging Completed 3-4-88

LEASE OPERATOR Conoco Inc.

ADDRESS 3817 NW Expressway, Oklahoma City, OK 73112

PHONE# (405) 948-3100 OPERATORS LICENSE NO. 05916

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Carl Goodrow

Is ACO-1 filed? No If not, is well log attached? Well log sent in with Form CP-1 on 12-16-87

Producing Formation Sanding-KC Depth to Top 3656' Bottom 3804' T.D. 3871'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
L-KC 'B-D'	-	3656	78	10 3/4"	245'	None
L-KC 'E'	-	3691	3700	7"	3869'	None
L-KC 'H'	-	3740	5'			
L-KC 'J'	-	3776	85			
L-KC 'K'	-	3799	3804			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

All wireline & perforate csg @ 1390' w/3 shots. All and pumped 250 lbs econolite and 5 lbs hulls down 7" csg @ 3 3/4 BPM @ 500 psi. Pmp'd 50 lbs econolite down 10 3/4" surface pipe. TC @ 78'. Dumped 1/2 cu yd in 7" csg and capped well 5' below ground level. Cleaned and leveled location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton Services License No. 5387

Address PO Box 579, Great Bend, KS 67530

STATE OF Oklahoma COUNTY OF Oklahoma, ss.

Kevin S. Vogel

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters hereinafter stated, and that the log of the above-described well as filed that the same are true and correct, so that the same may be used as evidence in any proceeding.

RECEIVED
 STATE CORPORATION COMMISSION
 3-11-88
 MAR 11 1988

Signature) Kevin S. Vogel

(Address) 3817 NW Expressway, OKC, OK 73112

SUBSCRIBED AND SWORN TO before me this 10th day of March, 19 88

CONSERVATION DIVISION
 Wichita, Kansas

Kathy J. Courtney
 Notary Public

My Commission Expires: 12/23/90