

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-137-20,373-00-00

LEASE NAME Reimann "B"

WELL NUMBER 1

4,290 Ft. from S Section Line

990 Ft. from E Section Line

SEC. 15 TWP. 5 RGE. 22 (E) or (W)

COUNTY Norton

Date Well Completed 2-3-91

Plugging Commenced 2-3-91

Plugging Completed 2-3-91

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 W. 12th, Hays, Ks. 67601

PHONE#(913) 628-3834 OPERATORS LICENSE NO. 5655  
5252

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-14-90 (date)

by Marvin Miller (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3,558'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	224'	Cmtd. w/165 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Fill hole w/heavy mud. Push bridge plug to 1,700', pump 25 sax cement down drill pipe. Push bridge plug to 1,040', pump 100 sax cement down drill pipe. Push bridge plug to 275', pump 40 sax cement down drill pipe. Push bridge plug to 40', dump 10 sax on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Shields Drilling Co. License No. 164

Address Shields Bldg., Russell, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman, Sec.-Treas. (Employee of ~~Operator~~ Contractor or ~~Operator~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack P. Beeman, Sec - Treas

(Address) Shields Bldg., Russell, KS. 67665

RECEIVED  
STATE CORPORATION COMMISSION

2-25-91  
FEB 25 1991

SUBSCRIBED AND SWORN TO before me this 18th day of February, 19 91

Ruth Phillips  
Notary Public

COMMISSION DIVISION

My Commission Expires:

