

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-137-20,245-00-00

LEASE NAME Watkins

WELL NUMBER #5

4950 Ft. from S Section Line

660 Ft. from E Section Line

SEC. 34 TWP. 5s RGE. 21 (X) or (W)

COUNTY Norton

Date Well Completed 9/18/81

Plugging Commenced 9:00 A.M. 7/12/90

Plugging Completed 10:30 A.M. 7/12/90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR The Dane G. Hansen Trust

ADDRESS P. O. Box 187, Logan, Kansas 67646

PHONE# (913) 689-4816 OPERATORS LICENSE NO. 5285

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 12, 1990 (date)

by Gilbert Balthazor (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? We do not have one.

Producing Formation Reagan Sand Depth to Top, 3699 Bottom 3705 T.D. 3705

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	200	None
				5 1/2"	3699	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Down 5 1/2" casing at 1000# Max. pressure, mixed 4 sks. hulls with 275 sks. cement,
and shut in at 800#. Down annulus (8 5/8" csg.), at 700# Max. pressure, mixed
1 sk. hulls with 75 sks. cement, and shut in at 400#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P. O. Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF PHILLIPS, ss. Wichita, Kansas

Harold Parsons (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Harold Parsons

(Address) P. O. Box 187, Logan, Kansas 67646

SUBSCRIBED AND SWORN TO before me this 18th day of July, 1990



Betty Jane Bittel Notary Public

My Commission Expires: July 17, 1992.