

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-127-00761-00-00

API NUMBER 15-N/A

LEASE NAME Veeh A

WELL NUMBER 6

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

4950 Ft. from S Section Line

330 ~~4950~~ Ft. from E Section Line

LEASE OPERATOR OXY USA Inc.

SEC. 36 TWP. 5S RGE. 21 (x) or (W)

ADDRESS P. O. Box 26100

COUNTY Norton

PHONE# (405) 749-2309 Operators License #5447

Date Well Completed 7/13/46

Character of Well Oil

Plugging Commenced 4/27/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4/27/95

The plugging proposal was approved on 11/10/94 (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3634 Bottom 3637 T.D. 3637

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3634	3637	8 5/8"	208	
				5 1/2"	3635	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set.

Perf @ 1105-06 & 1805-06. Mixed & pumped 50sks 60/40 pozmix w/10% gel 1/4# sk Flocele & 400# hulls. Top 5 1/2" csg started leaking, shut down. Pumped cmt down 5 1/2" same mix. Pressured to 600# w/255sks down & held @ 400#. Hooked to 8 5/8-5 1/2 annulus & pumped 75sks @ 600# press w/no hulls. Held @ 400#. Total 330 sks cement & 400# hulls.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) [Signature]

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 95

[Signature]  
Notary Public

My Commission Expires: 7-14-95



MAY 05 1995  
05-05-1995