

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-137-00721-00-00

API NUMBER 15-N/A

LEASE NAME Veeh A

WELL NUMBER 13

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

4290 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 36 TWP. 5S RGE. 21 (X) of (W)

COUNTY Norton

Date Well Completed 6/21/57

Plugging Commenced 4/28/95

Plugging Completed 4/28/95

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/94 (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3660 Bottom 3676 T.D. 3676

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3660	3676	8 5/8"	240	
				5 1/2"	3660	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

Perf @ 1131-32 & 1831-32. Ran in 2 3/8" tbq to 3589'. Mixed & pumped 77sks 60/40 pozmix w/10%gel w/ 1/4# Flocele per sk w/150# hulls. Pulled to 2388' pumped 77sks & 150# hulls. Pulled tbq to 1188' Hook to 8 5/8"- 5 1/2" annulus & pumped 75sks cmt w/50# hulls. Pumped to 400# held @ 250#. Cut off csq 5' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) *Jerry Ledlow*

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 1995

Notary Public

My Commission Expires: 7-14-95