

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-127-00720-00-00

API NUMBER 15-N/A

LEASE NAME Veeh A

WELL NUMBER 12

TYPE OR PRINT
NOTICE: Fill out completely
and return to
Cons. Div. Office within
30 days.

2970 Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 36 TWP. 5S RGE. 21 (X) or (N)

COUNTY Norton

Date Well Completed 5/29/95

Plugging Commenced 4/28/95

Plugging Completed 4/28/95

LEASE OPERATOR OXY USA Inc.

ADDRESS P. O. Box 26100

PHONE# (405) 749-2309 Operators License #5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/94 (date)

by Herb Deines, Bruce Bayse (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3651 Bottom 3655 T.D. 3655

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3651	3655	8 5/8"	240	
				5 1/2"	3651	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Perf @ 1120-21 & 1805-06. Hooked up to 5 1/2" csg, pumped 60/40 pozmix w/10% gel w/ 1/4# Flocele per sk w/400# hulls. Pumped 255 sks cmt, shut in @ 1200 PSI. Held @ 400#. Hooked up to 8 5/8"-5 1/2" annulus & pumped 105sks cmt w/100# hulls same cement. Shut in & held 75#. Cut csg off 5' below ground level.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307, Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

05-05-1995

(Signature) *Jerry Ledlow*

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 95

Cari Allen
Notary Public

My Commission Expires: 7-14-95