

15-137-00315-00-00

Give All Information Completely
Make Required Affidavit.
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

WELL PLUGGING RECORD

Norton County. Sec. 36 Twp. 5S Rge. (E) 21 (W)

Location as "NE/CNW/SW" or footage from lines 990' FNL & 990' FFL
Lease Owner Cities Service Oil Company
Lease Name Veeh "A" Well No. 10
Office Address Box 553 Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 11-18 19 49
Application for plugging filed 8-23 19 71
Application for plugging approved 8-24 19 71
Plugging commenced 9-16 19 71
Plugging completed 9-22- 19 71
Reason for abandonment of well or producing formation Non productive

If a producing well is abandoned, date of last production 3-28 19 70
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Nichols
Producing formation Reagan Depth to top 3655 Bottom 3659' Total Depth of Well 3659 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	210'	None
				5 1/2"	3677'	588'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled W/sand 3659' to 3615', 5 sacks cement 3615' to 3580' Shot 5 1/2" Casing off at 691' Pulled 588' of 5 1/2" casing. Filled hole W/mud 3580 to 1750', 5 sacks hulls 1750' to 1550'; 13 sacks gel 1550' to 1030' 105 sacks of cement 1030' to 750', 12 sacks of gel 715'-235', 25 sacks of cement 235' to surface. Max. pressure 200 psi Plugging completed 9-22-71

RECEIVED
STATE CORPORATION COMMISSION
OCT 01 1971
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address P. O. Box 405 Chase, Kansas 67524

STATE OF Kansas, COUNTY OF Russell, ss.
E. W. Peterman (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Box 553 Russell, Kansas 67665
(Address)

Subscribed and Sworn to before me this 30th day of September, 19 71
James S. Kyger
Notary Public.

