

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-N/A

LEASE NAME Veeh A

15-137-00735-00-00

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to  
Cons. Div. Office within  
30 days.

WELL NUMBER 4

3630 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 36 TWP. 5S RGE. 21 (X) or (W)

LEASE OPERATOR OXY USA Inc.

COUNTY Norton

ADDRESS P. O. Box 26100

Date Well Completed 4/12/46

PHONE# (405) 749-2309 Operators License #5447

Plugging Commenced 4/27/95

Character of Well Oil

Plugging Completed 4/27/95

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11/10/94 (date)

by Dennis Hamel (KCC District Agent's name).

Is ACO-1 filed? no If not, is well log attached? no

Producing Formation Reagan Depth to Top 3625 Bottom 3628 T.D. 3628

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled Out
Reagan	Oil	3625	3628	8 5/8"	206	
				5 1/2"	3620	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from        feet to        feet each set.

Perf @ 1096-97 & 1796-97. RIH w/ 2 3/8" tbq set @ 3589'. Mixed & pumped 77sks 60/40 pozmix w/10%gel & 1/4#Flocele per sk, added 150# hulls. Pumped 77sks same mix, pumped 83sks w/100# hulls POH w/ last of tbq. Tied onto 5 1/2csg & pumped 30sks. Pressured to 200# & held. Hooked to 8 5/8" - 5 1/2" annulus, pumped 75sks cmt w/100# hulls Shut in @ 100# & held. (See back of form)  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Hi-Plains Production Inc. License No. 8003

Address P. O. Box 307 , Logan, KS 67646

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF OKLAHOMA COUNTY OF OKLAHOMA, ss.

Jerry Ledlow (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Jerry Ledlow

(Address) P. O. Box 26100, OKC, OK 73126-0100

SUBSCRIBED AND SWORN TO before me this 2nd day of May, 19 95

Cari Allen  
Notary Public

My Commission Expires: 7-14-95

Cut off csg 5' below ground level.