

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, KS 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-137-00599-00-00  
API NUMBER 15-137-07-31-57

LEASE NAME Kitzke

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Comm. Div.  
office within 30 days.

WELL NUMBER 7

4950 ft. from S Section Line

2970 ft. from E Section Line

SEC. 36 TWP. 05 RGE. 21  or  (W)

COUNTY Norton

Date Well Completed 08/07/57

Plugging Commenced 11/07/96

Plugging Completed 11/07/96

LEASE OPERATOR OXY USA Inc.

ADDRESS P.O. Box 300; Tulsa, OK 74102-0300

PHONE # (918) 561-2211 OPERATOR'S LICENSE NO. 5447

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply)

The plugging proposal was approved on October 22, 1996 (date)

by Dennis L. Hamel

Is ACO-1 file? No If not, is well log attached? Yes

Producing Formation Reagan Depth to Top 3647' Bottom 3648' T.D. 3648'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORDS

Formation	Content	From	To	Size	Put in	Pulled out ...
Reagan	Oil	3647'	3648'	8-5/8"	240'	0
				5-1/2"	3646'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from     feet to     feet each set.

Dug out csg & orange peeled 5-1/2" to 8-5/8" csg. Install 2" riser to surface. This well has a D.V. tool @ 1821'. Cmt w/ 400 sxs 50/50 pozmix & 200 cu ft strate-crete. MIRU Murfin Drilling, RIH w/ 2-3/8" tbg. Open ended to 3600'. Pumped 65 sxs MIDCON 2 w/ 2% C.C. & 300# cottonseed hulls. Pulled 48 jts. to 2100'. Pumped 65 sxs cmt & 200# hulls. Pulled tbg to 600'. Pumped 30 sxs cmt. and cir to surface. (continued one back)

Name of Plugging Contractor Halliburton Energy Services License No. 5287

Address 1102 E. 8th St.; Hays, KS 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OXY USA Inc.

STATE OF Kansas COUNTY OF Rooks, ss.

Kenneth R. Curry (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED  
KANSAS CORPORATION COMMISSION


02-18-1997 (Signature) [Signature]

FEB 18 1997 (Address) P.O. Drawer D; Plainville, KS 67663

SUBSCRIBED AND SWORN TO before me this 14 day of February, 1997

CONSERVATION DIVISION  
WICHITA, KS

[Signature]  
Notary Public



My Commission Expires: May 20, 2000

Additional plugging report information on the Kitzke #7.

POOH w/ rest of tbg. Hooked up to 5-1/2" csg and pumped 25 sxs cmt. Max P.S.I. 600#. S.I.P. 600#. Hooked up to 8-5/8" csg and pumped 5 sxs MIDCON 2 cmt w/ 2% C.C. and zero lbs hulls. Max P.S.I. 400#. Rig down. Total cmt used 190 sxs.

# WELL RECORD

15-137-00599-00-00

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Cities Service Oil Co. WELL # 7 FARM Kitoko

LOCATION 330' S. and 330' W. of N/4 Cor., Section 36, Township 5, Range 21W.

ELEV. 2219 (2216 Cr.) CO. Norton STATE Kansas

IP. Physical potential 285 oil, 6 water, 24 hours, September 11, 1957.

PERFS. ....

FRAC. .... ACID None

T.D. 3648' PBTD. .... GRAV/GOR. ....

DRLG. COMM. July 31, 1957 COMP. August 7, 1957 CONTRACTOR Lehmann-Johnson Drilling Co., Inc.

**CASING RECORD:**

8-5/8" at 240' with 200 sacks cement.  
 5-1/2" at 3646' with 200 sacks cement.  
 DV tool at 1819' with 400 sacks cement and  
 200 cubic feet Stratacrete.

**FORMATION RECORD:**

sand and shale	0-240
shale and sand	1310
shale, sand and lime	1790
anhydrite	1825
shale	2160
lime and shale	2385
shale	2575
lime and shale	2745
lime	3639
cored lime (rec. 5')	3644
cored lime & sand (rec. 2'4")	3647
cored sand (rec. 2'9")	3650
3650 Rotary T.D. - 3648 S.L.H.	

Corr. Topeka	3184
Corr. Heebner	3363
Corr. Dodge	3389
Corr. Lansing	3407
Corr. Base Kansas City	3598
Corr. Gorham	3644
Corr. Reagan	3647
Penetration	1'
T.D.	3648'

**Fill-up:**

75' oil in 15 minutes.  
 364' oil in 1 hour 5 minutes.  
 608' oil in 1 hour 40 minutes.  
 803' oil in 2 hours 10 minutes.  
 2562' oil in 19 hours.

**Slope Tests (Syfo):**

500' - 0°  
 1000' - 0°  
 1500' - 1°  
 2000' - 1°  
 2500' - 1°

7-7/8" Rotary hole.

RECEIVED  
 KANSAS CORPORATION COMMISSION

FEB 18 1997

CONSERVATION DIVISION  
 WICHITA, KS