

15-137-00075-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM

Lease Owner Jones, Shelburne & Farmer Address Russell, Kansas
(Applicant)
Lease (Farm Name) Carl Dwyer Well No. 1
Well Location SE SE NE Sec. 26 Twp. 5 Rge. 24 (E)-(W)
County Norton Field Name (if any) Wildecat
Total Depth 3970' Oil Gas Dry Hole X
Was well log filed with application? Yes. If not, explain:

Date and hour plugging is desired to begin 1-8-52

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully any exceptions desired.
(Use an additional sheet if necessary)

Name of the person on the lease in charge of well for owner
Marion Helberg Address Lenora, Kansas

Name of Plugging Contractor Empire Drilling Company
Address 1121 Union Natl. Bank Bldg., Wichita, Kans.

Invoice covering assessment for plugging this well should be sent to Jones, Shelburne & Farmer Address Russell, Kansas

and payment will be guaranteed by applicant.

Jones, Shelburne & Farmer
By: Dan J. Kornfeld
Dan J. Kornfeld
Acting Agent

Date 1-8-52

PLUGGING PERMIT
JAN 21 1952
FILE SEC 26 T 5 R 24
BOOK PAGE 136 LINE 38
DIVISION
WICHITA, KANSAS
1-21-52

COMPANY: Jones, Shelburne & Farmer
 Russell, Kansas

CONTRACTOR: Empire Drilling Company
 Wichita, Kansas

FARM: CARL DWYER No. 1

LOCATION: SE SE NE 26-5-24
 Norton County, Kansas

COMMENCED: 12-28-51

COMPLETED: 1-8-52

0	to	60	Clay
60-	to	75	Sand
75	to	500	Shale, shells and sand
500	to	1990	Shale and shells
1990	to	2020	ANHYDRITE
2020	to	2560	Shale and shells
2560	to	2650	Shale and Lime
2650	to	3545	Shale and Lime
3545	to	3576	Lime
3576	to	3760	Lime
3760	to	3933	Shale & Lime
3933	to	3970	Lime, shale and chert T. D.

Set 165' of 8-5/8" surface pipe.
 Cemented with 135 sacks cement.

TOPS: Anhydrite 1990'; Topeka 3302'; Toronto 3536'; Lansing 3540';
 base Kansas City 3732'; Conglomerate 3884'; Arbuckle 3920';
 solid Arbuckle 3925'.
 T. D. 3970'.

DRILL STEM TEST: #1 3554'-76'. Open 1-hour. Good blow. 120' watery
 drilling mud. Flecks of oil. 1150# bottom hole
 pressure.

DRILL STEM TEST: #2 3575'-3620'. Open 1-hour. Weak blow. 70' watery
 drilling mud. 990# bottom hole pressure.

ELEVATION: 2369'. K-B.

DRY.

1-21-52

C E R T I F I C A T E

I, Dan J. Kornfeld, do hereby certify that the above and foregoing
 is a true and correct copy of the log of the Carl Dwyer No. 1 well,
 as reflected by the files of Empire Drilling Company.

Dan J. Kornfeld
 Dan J. Kornfeld

Subscribed and sworn to before me, a Notary Public, within and for
 County of Sedgwick, State of Kansas, this 14th day of January, 1952.

Evelyn V. North
 Notary Public

My commission expires Dec. 22, 1954.

PLUGGING
 FILE SEC 26T 5 R 244
 BOOK PAGE 136 LINE 38



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-137-00075-00-00

January 9, 1952

Well No. 1
Lease Dyer
Description SE SE NE 26-5-21W
County Norton
File No. 136-38

Jones, Shelburne & Farmer, Inc.
Russell, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 328, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR