

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-137-00063-00-00

WELL PLUGGING APPLICATION FORM

Lease Owner Peel-Hardman Address P. O. Box 359, Hoisington, Kansas
(Applicant)

Lease (Farm Name) Allen Well No. 1

Well Location SW SW SW Sec. 11 Twp. 5S Rge 24 (E)-(W) W

County Norton Field Name (if any) _____

Total Depth 3835' Oil _____ Gas _____ Dry Hole X

Was well log filed with application? No. If not, explain: _____

Well just completed as a dry hole

Date and hour plugging is desired to begin 8:00 A. M. July 15, 1951

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission, or with the approval of the following exceptions: Explain fully State exceptions desired.

(Use an additional sheet if necessary) _____

RECEIVED
STATE CORPORATION COMMISSION
AUG 14 1951
CONSERVATION DIVISION
Wichita, Kansas

8-14-51

Name of the person on the lease in charge of well for owner _____

Glenn W. Peel Address P. O. Box 359, Hoisington, Kansas

Name of Plugging Contractor Glenn W. Peel

Address P. O. Box 359, Hoisington, Kansas

Invoice covering assessment for plugging this well should be sent to

Peel-Hardman Address P. O. Box 359, Hoisington, Kansas

and payment will be guaranteed by applicant.

PEEL-HARDMAN
P. O. Box 359
HOISINGTON, KANSAS

BY: [Signature]
Applicant or Acting Agent

Date 7-15-51

PLUGGING
FILE SEC 11 T 5 R 24
BOOK PAGE 104 LINE 34

7

DRILLER'S LOG

Company: Peel-Hardman
Farm: Allen Well No. 1
Comm: 5-13-51 Comp: 5-21-51

SW SW SW
Sec. 11, Twp. 5S, Rge. 24W
County: Norton,
Kansas

Total Depth: 3835'
Contractor: Glenn W. Peel
Casing:
8 5/8" 173' cem.
5 1/2" 3597' cem.

Elevation:
Production:

Figures below indicate bottom of formations

Surface Soil	0 -	20
Shale		100
Shale & Shells		1175
Sand		1400
Shale		1440
Shale & Sand		1875
Anhydrite		1925
Shale & Sand		1970
Shale & Shells		2695
Lime & Shale		3395
Lime		3545
Lime & Shale		3830
Lime		3835
Total Depth		3835

This is to certify that the above information is, to the best of our knowledge, true and correct.

PEEL-HARDMAN

BY: Wm Herbert

SUBSCRIBED AND SWORN to before me this 16th day of August, 1951.

My commission expires June 4, 1955
Marion M. Herbert
Notary Public

Moved cable tools in on May 26, 1951, bailed hole and drilled cement, Lane-Wells perforated with 24 shots from 3554' to 3558', acidized with 1000 gals., set retainer @ 3520' and squeezed with 150 sacks cement, drilled retainer and cement, perforated with Lane-Wells from 3554' to 3558', acidized with 1000 gals., swabbed, bailed and tested, acidized with 3000 gals., set Lane-Wells plug @ 3547', perforated with 34 shots from 3539' to 3543', squeezed with 50 sacks cement, drilled cement and Halliburton retainer, perforated with 12 shots from 3539' to 3543', acidized with 1000 gals., bailed and tested, perforated with 29 shots from 3532' to 3539', and with 6 shots from 3543' to 3544 1/2', acidized with 3000 gals., swabbed and tested, set Lane-Wells plug @ 3524', perforated with 24 shots from 3479' to 3483', acidized with 1000 gals., swabbed and tested, perforated with 12 shots from 3468' to 3472' and with 12 shots from 3443' to 3446', squeezed off water, swabbed hole dry, drilled retainer and cement, perforated with 24 shots from 3442' to 3451' and 16 shots from 3441' to 3445', acidized with 1000 gals., swabbed and tested, completed as a dry hole June 16, 1951.

PLUGGING
FILE SEC. 11, T. 5, R. 24W
PAGE 10 of 34

AUG 14 1951
CONSERVATION DIVISION
Wichita, Kansas



STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
800 BITTING BUILDING
WICHITA, KANSAS

15-137-00063-00-00

August 14, 1951

Well No. 1
Lease Allen
Description SW SW SW 11-5-24W
County Horton
File No. 102-34

Peel-Hardman, Producers
Box 359
Holsington, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas.

STATE CORPORATION COMMISSION
CONSERVATION DIVISION

BY: J. P. Roberts
J. P. ROBERTS

cc: DISTRICT PLUGGING SUPERVISOR