

15-137-00645-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
211 NORTH BROADWAY
WICHITA, KANSAS

WELL PLUGGING APPLICATION FORM
File One Copy

Lease Owner Cities Service Oil Co. Address Bartlesville, Oklahoma
(Applicant)
Lease (Farm Name) Fox Well No. 1
NE SE NE
Well Location 1650'S 330'W NE Corner Sec. 35 Twp. 5 Rge. 21 (E) (W)
County Norton Field Name (if any) _____
Total Depth 3687' Oil ___ Gas ___ Dry Hole X
Was well log filed with application? ___ If not, explain: will accompany
plugging record.

Date and hour plugging is desired to begin as soon as possible.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of the person on the lease in charge of well for owner F. P. McCollum,
Cities Service Oil Co. Address Box 175, Logan, Kansas

Plugging Contractor Lohmann & Johnson

Plugging Contractor's Licence No. _____

Address Evansville, Indiana

Invoice covering assessment for plugging this well should be sent to _____

Mr. M. M. Hardin, Box 553 Address Russell, Kansas

and payment will be guaranteed by applicant.

11-08-1957

M M Hardin
Applicant or Acting Agent

RECEIVED

Date 11-7-57

PLUGGING
FILE SEC. 35 T. 5 R. 21W
BOOK PAGE 59 LINE 37

WELL RECORD

15-137-00645-00-00

WILDCAT.....

DISCOVERY.....

POOL.....

COMPANY Citizen Service Oil Company WELL # 1 FARM Fox

LOCATION 1650'S and 330' W. of NE Cor.
Section 35, Township 5, Range 21W.

ELEV. 2249 (2247 Gr.) CO. Norton STATE Kansas

IP. None. Dry Hole. P. & A. November 6, 1957.

PERFS.....

FRAC..... ACID None

T.D. 3687' PBTD..... GRAV/GOR.....

DRLG. COMM. October 27, 1957 COMP. November 5, 1957 CONTRACTOR Lohmann-Johnson Drilg. Co., Inc.

CASING RECORD:

8-5/8" at 240' with 200 sacks cement.

FORMATION RECORD:

sand	0-40
shale	240
shale and sand	1000
shale	1809
anhydrite	1850
shale	2072
shale and lime	2240
lime and shale	2450
shale	2700
lime and shale	2860
shale and lime	2950
lime	3673
Cored lime & sand (Rec. 3' 10")	3677
Cored lime and sand (Rec. 2' 10")	3680
Cored granite wash (Rec. 2')	3682
granite wash	3687 T.D.

Topoka	3216
Heebner	3399
Dodge	3425
Lansing	3441
Base Kansas City	3631
Gorham	3676
Granite Wash	3680
Pen.	7'
T.D.	3687

D.S.T. 3675-87, open 1 hour, rec. 3' oil and 37' heavily oil-cut mud; B.M.P. 370# in 30 minutes.

Slope Tests (Srfo):

500'	- 0°
1000'	- 1°
1500'	- 1°
2000'	- 1°
2500'	- 1°
3000'	- 2°

7-7/8" Rotary hole.

PLUGGING

FILE SEC 35 T 5 R 21W

BOOK PAGE 59 LINE 37

RECEIVED
 STATE OF KANSAS COMMISSIONER OF GEOL.

NOV 20 1957

CONSULTING ENGINEER
 WICHITA, KANSAS

STATE OF KANSAS
State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas
November 8, 1957

15-137-00645-00-00


Well No.	1
Lease	Fox
Description	NE SE NE 35-5-21W
County	Morton
File No.	59-37

Otties Service Oil Company
c/o R. M. Hardin
Box 553
Russell, Kansas

Gentlemen:

This letter is your authority to plug the above subject well, in accordance with the Rules and Regulations of the State Corporation Commission. When you are ready to plug this well, please contact our District Plugging Supervisor, Mr. Eldon Petty, Box 326, Hays, Kansas Ph. 4-3718

Very truly yours,


Jewel M. Ogden
Director of Conservation Division

cc:
District Plugging Supervisor