

15-137-00315-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
500 INSURANCE BUILDING
212 NORTH MARKET
WICHITA, KANSAS 67202

FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

RECEIVED
STATE CORPORATION COMMISSION
08-24-1971
AUG 24 1971
CONSERVATION DIVISION
Wichita, Kansas

Lease Owner Cities Service Oil Company

Address Box 553 Russell, Kansas 67665

Lease (Farm Name) Veeh "A" Well No. 10

Well Location SW NE NE 990' FNL & 990' FEL Sec. 36 Twp. 5S Rge. 21 (E) (W) X

County Norton Field Name (If Any) Ray Pool

Total Depth 3659' Oil Well X Gas Well Input Well SWD Well D & A

Well Log filed with application Yes or Well Log filed with Plugging Supervisor

Date and hour plugging is desired to begin 8-26-71 10:00 A.M.

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations W. E. Anderson

Address Box 277 Logan, Kansas 67646


Plugging Contractor Knight Casing Pulling Co., Inc. License No.

Address P. O. Box 405 Chase, Kansas 67524

Invoice covering assessment for plugging this well should be sent to E. W. Peterman

Address Box 553 Russell, Kansas 67665

and payment will be guaranteed by applicant.

Signed:  E. W. Peterman
Applicant or Acting Agent

Date: August 23, 1971

WELL RECORD 15-137-00315-00-00

Company Cities Service Oil Co. Well No. 10 Farm Veech
 Location 990' South and 990' West of NE Corner Sec. 36 T. 5 R. 21W
 Elevation ff. 2230 (2228 Gr.) County Norton State Kansas
 Drlg. Comm. November 3, 1949 Contractor R. W. Rine Drilling Company
 Drlg. Comp. November 16, 1949 Acid None
 T. D. 3659' Initial Prod. Physical Potential: 165 oil, 7 water, 24 hrs. (11-18-49)

CASING RECORD:

3-5/8" @ 205' cem. 250 sx cement
 5-1/2" @ 3655' cem. 150 sx cement

FORMATION RECORD:

sand & clay	0-145
shale	205
shale & sand	1810
anhydrite	1845
shale & shells	2860
shale & lime	3185
lime	3645
cored lime & shale, rec.	
2'3"	3648
cored lime & sand, rec.	
4'9"	3653
3653 RTD = 3657 SIM	
sand	3659 T. D.

Corr. Top Topeka	3207'
Corr. Top Lansing	3420'
Corr. Top Reagan	3654'
Penetration	5'
Total Depth	3659'

Fillup: 345' oil in 1 hr.
 560' oil in 1-1/2 hrs.
 860' oil in 2-1/2 hrs.
 1060' oil in 3-1/2 hrs.
 1185' oil in 4-1/2 hrs.
 1365' oil in 5-1/2 hrs.
 1490' oil in 6-1/2 hrs.
 1690' oil in 7-1/2 hrs.
 1800' oil in 8-1/2 hrs.
 1890' oil in 9-1/2 hrs.
 2070' oil in 11-1/2 hrs.
 2405' oil in 17-1/2 hrs.

SXFO: 500' 0°
 1000' 1°
 1500' 1°
 2000' 0°
 2500' 0°
 3000' 1°

7-7/8" rotary hole.

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 24 1971
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

August 24, 1971

15-137-00315-00-00

WELL PLUGGING AUTHORITY

Well No.	10
Lease	Veeh "A"
Description	SW NE NE 36-5-21W
County	Norton
Total Depth	3659
Plugging Contractor	Knight Casing Pulling Co.


Cities Service Oil Company
Box 553
Russell, Kansas 67665

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,


J. Lewis Brock, Administrator

Mr. W. L. Nichols Box 157 Morland, Kansas
is hereby assigned to supervise the plugging of the above named well.