

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 039 - 204 29 - 00 - 00 (of this well)
Lease Owner F & M Oil Company
Address 505 Union Center, Wichita, Kansas 67202
Lease (Farm Name) Gillespie Well No. 1
Well Location W/2 SW SW Sec. 11 Twp. 5S Rge. 27W (E) (W) X
County Decatur Total Depth 3880' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 7:00 p.m., November 7, 1978

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:

Bill Craig Address 702 South 2nd St., Hill City, KS
Plugging Contractor Abercrombie Drilling, INC. License No.
Address 801 Union Center, Wichita, Kansas 67202

Invoice covering assessment for plugging this well should be sent to:

Name F & M Oil Company
Address 505 Union Center, Wichita, KS 67202

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1978
11-17-78
CC

Signed: Jack L. Partridge

Applicant or Acting Agent
Jack L. Partridge, Asst. Sec.-Trea
Date: November 15, 1978

CONTRACTOR'S WELL LOG

15-039-20429-00-00

OPERATOR: F & M Oil Company
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: Gillespie #1
 LOCATION: W/2 SW SW, Section 11-5S-27W
 Decatur County, Kansas
 SPUD DATE: October 30, 1978
 COMPLETION DATE: November 7, 1978

0	265	Surface soil, sand & shale
265	615	Shale
615	1550	Sand & shale
1550	2258	Shale & Sand
2258	2291	Anhydrite
2291	2791	Shale
2791	3085	Lime & Shale
3085	3228	Shale
3228	3540	Lime & Shale
3540	3650	Shale & lime
3650	3705	Lime
3705	3725	Shale
3725	3880	Lime
	3880	Rotary Total Depth

Spud hole at 11:00 p.m., October 30, 1978. Drilled 265' of 12 1/4" hole. Ran 7 joints of 8 5/8" - 28# used casing. Set at 264' with 200 sacks of 60/40 posmix, 3% Ca.Cl., 2% gel. Cement did circulate. Plug was down at 4:45 a.m. on October 31, 1978.

T.D. 3880'. Set 1st plug at 1300' with 70 sacks, 2nd plug at 240' with 20 sacks, 3rd plug at 40' solid bridge with 10 sacks. Cemented with 50/50 posmix, 6% gel. Plug was down at 7:00 p.m., November 7, 1978.

SAMPLE TOPS:

Anhydrite 2258'
 B/Anhydrite 2291'

RECEIVED
 STATE CORPORATION COMMISSION

NOV 17 1978

11-17-78

REGISTRATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) ss
 COUNTY OF SEDGWICK)

Jack L. Partridge, Assistant Secretary-Treasurer of Abercrombie Drilling, Inc. does hereby state that the above and foregoing is a true and correct copy of the log of the Gillespie #1, W/2 SW SW, Section 11-5S-27W, Decatur County, Kansas.

ABERCROMBIE DRILLING, INC.

BY Jack L. Partridge

Subscribed and sworn to before me, a Notary Public, in and for the county and state aforesaid, as of this 15th day of November, 1978.



Sherrie L. Brooks
 Sherrie Brooks, Notary Public

My commission expires 8-21-82.

State of Kansas



15-039-20429-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

November 14, 1978

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Gillenspie
Description	W/2 SW SW Sec. 11-5-27W
County	Decatur
Total Depth	3880'
Plugging Contractor	Abercrombie Drilling, Inc.


F & M Oil Co., Inc.
505 Union Center
Wichita, Kansas 67202

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,


J. Lewis Brock, Administrator

Mr. Gilbert Balthazor, P.O. Box 9, Route #1, Palco, Kansas 67657
is hereby assigned to supervise the plugging of the above
named well.