

15-039-~~1955~~ 00-00-01
00575

BARNETT DRILLING, INC.

LOG OF KOERPERICH WELL NO. 1

NW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$, SECTION 11-5S-27W, DECATUR COUNTY, KANSAS

Commenced: 4-3-54

Feely Lansing KC Permit No. 6

Completed: 4-14-54

<u>Formation</u>	<u>From</u>	<u>To</u>	<u>Remarks</u>
Surface Clay	0	50	
Sand	50	62	
Shale	62	100	
Sand	100	180	
Blue Shale	180	207	Set 8-5/8" surface pipe at 207 feet, cemented with 150 sacks.
Blue Shale	207	255	
Shale and Shells	255	725	
Sand	725	775	
Shale	775	1245	
Sandy Lime and Shale	1245	1300	
Shale and Shells	1300	1520	
Shale	1520	1550	
Sand	1550	1675	
Shale	1675	2203	
Anhydrite	2203	2240	
Shale and Shells	2240	2690	
Lime and Shale	2690	2950	
Lime	2950	3055	
Lime and Shale	3055	3170	
Lime	3170	3840	
Total Depth		3840	Set 5 1/2" casing at 3690 feet, cemented with 125 sacks.

RECEIVED
STATE CORPORATION COMMISSION
OCT 26 1971
CONSERVATION DIVISION
Wichita, Kansas

10-26-71

CERTIFICATE

I, F. R. Stubblefield, of Barnett Drilling, Inc., certify that to the best of my knowledge and belief, the above is a true and correct log of the Koerperich Well No. 1, located in the NW $\frac{1}{4}$ NW $\frac{1}{4}$ NE $\frac{1}{4}$ of Section 11-5S-27W, Decatur County, Kansas.

F. R. Stubblefield

Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 21st day of May, 1954.

Mildred F. Willis

My commission expires February 27, 1956.

250

State of Kansas



15-039-⁰⁰⁵⁷⁵~~74550~~-00-⁰¹~~210~~

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

October 26, 1971

WELL PLUGGING AUTHORITY

Well No.	6
Lease	Feely Lansing-KC Unit
Description	NW NW NE Sec. 11-5S-27W
County	Decatur
Total Depth	3840'
Plugging Contractor	Unknown

Continental Oil Company
3535 NW 58th Street
Oklahoma City, Oklahoma 73112

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Very truly yours,

J. Lewis Brock
J. Lewis Brock, Administrator

Mr. W. L. Nichols, P. O. Box 157, Morland, Kansas 67650
is hereby assigned to supervise the plugging of the above named well.