

State of Kansas



15-039-20023-06-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1967

9-6-67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Cook of Abercrombie Drlg. Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling Inc.,

Complete Address: 801 Union Center Wichita, Kansas

Lease Name: Boland Well No. 1

Location: 100' S NE NW NE Sec. 15 Twp. 5 Rge. 27 (E)(W) X

County Decatur Total Depth 3824 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1500' and displace  
65 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and  
displace 10 sc cement thru drill pipe. Heavy mud to 40' set cementing  
plug, 1/4 sc hulls and ~~30~~ 5 sc cement to base of cellar. Plug rat  
hole with 2 sc cement.

Very truly yours,

Leo J. Massey  
Conservation Division Agent