

State of Kansas



15-039-20033-00-00

ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JAN 2 1969

CONSERVATION DIVISION  
Wichita, Kansas

1-2-69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Albert Unruh of Southwest Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston,

Complete Address: 425 First National Bank Building, Wichita, Kansas.

Lease Name: Feely Well No. 1

Location: NE-SW-SE Sec. 22 Twp. 5 Rge. (E)(W) 27

County: Decatur Total Depth 3930 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Unruh was instructed to plug the well as follows:

242'--8 5/8" Surface casing, cement circulated with 175 Sx.  
3929'--4 1/2" Casing cemented on bottom with 125 Sx. Top of cement @ 3440'.  
Top perforations from 3709' to 3713'.

Sand well back to 3650' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 35 sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent