



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
CONSERVATION DIVISION  
(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 31 1964  
8-31-64  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. J. W. Bolick of Continental Oil Co. has this date requested permission to plug the following described well:

Mr. Bolick guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: Box #267, Great Bend, Kansas.

Lease Name: C. E. Feely Well No. 1

Location: C NW SE NE 1650' FNL & 990' FEL Sec. 22 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3898 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Bolick was instructed to plug the well as follows:

255'--10 3/4" Surface pipe, cement circulated with 200 Sx.  
3833'--5 1/2" production casing cemented with 250 Sx. Well plugged back to 3690', top perforations @ 3666'.

Sand well back to 3650 and set 5 Sx. cement with dump bailer.  
Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2" / Pull 5 1/2" to 240' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10 Sx. cement to bottom of cellar.

Very truly yours,  
M. L. Nichols  
Conservation Division Agent