



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

SEP 30 1964
9-30-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Merle Herring of Barnes & Sons Pipe Pulling has this date requested permission to plug the following described well:

R. W. Shields
Mr. Herring guarantees payment of the plugging fee.

Operator's full Name: R. W. Shields.

Complete Address: 666 4th National Bank Bldg., Wichita, Ks.

Lease Name: C. E. Feely Well No. 1

Location: SE-SE-NE Sec. 22 Twp. 5 Rge. (E) (W) 27

County Decatur Total Depth 3860 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Herring was instructed to plug the well as follows:

175' -- 8 5/8" Surface pipe cement circulated.
3859' -- 5 1/2" Production casing cemented with 175 Sx. Well
plugged back to 3627. Top perforations from 3620' to 3616'.

Sand well back to 3600' and set 5 Sx. cement with dump bailer.
Circulate heavy gel mud @ 600'. Pull 5 1/2" to 540' and displace
20 Sx. cement thru 5 1/2". Pull 5 1/2" to 200' and displace 20 Sx.
cement thru 5 1/2". Pull 5 1/2", set bridge @ 35' and 10 Sx. cement
to bottom of cellar.

Very truly yours,

R. A. Nichols
Conservation Division Agent